Project Scope Statement

I. General Information

Project name: Future Tech Network Project number: 243

Project Manager name: Felicia Ainslie Date: 11/20/2018

II. Project Overview *Describe the product or service of the project, the reason the project was undertaken, and the purpose of the project.*

Future Tech Inc. is opening a new location that requires a private internal network to allow employees to connect with one another and the internet. This project will involve investing in hardware such as routers, modems, switches, computers, cabling, and servers. Software will also be included in these investments to ensure proper networking management is obtainable. In addition to acquiring these components, the network will need to be constructed to provide high-availability to Future Tech Inc.. The purpose for this project is to expand the organization's current customer base and increase profits by providing a reliable network for employees to use daily.

III. Project Goals and Objectives *Describe the project goals using the SMART (Specific, Measurable, Accurate and Agreed to, Realistic, Time Bound) formula. These goals will be used to measure and determine the project 's success at its conclusion.*

Develop a functional and private internal network that allows Future Tech Inc. to store data in different servers based on its purpose. This project will also allow employees to safely access the internet with the assistance of firewall rules, encryption techniques, and anti-virus/malware programs. The completed network should be launched by January 20th, 2019.

IV. Comprehensive List of Project Deliverables *These are the products or services that must be produced in order to fulfill the goals of the project. Deliverables should have measurable, verifiable results and outcomes. Identify critical success factors. Will map roughly to the work package Level of the WBS*

This private internal network will span three floors and cover roughly 16,000 square feet of space. There will need to be roughly one access point for every 1,600 square feet for the top two levels and a minimum of two access points on the lower level (Kaleem, 2017). Routers and switches will be utilized to connect devices to the network and a modem will be used to allow access to the internet. Servers will also be utilized to store customer and organization sensitive data. Technical policies will be developed to ensure the network and organization's security. Additional security measures will be taken to ensure that only authorized individuals can access the devices on site, intranet, data, and servers. These will include but may not be limited to physical and virtual locks, firewalls, and anti-virus/malware software.

Change Request Form effective 12/20/2018:

The first level, or lower level, will have a minimum of three access points.

V. Comprehensive List of Project Requirements *Requirements are the specifications of the deliverables.*

The finished network should provide each user with no less than 30mb download speeds and 5mb upload speeds. The top two floors will have absolutely no black out zones; however, the first floor only requires that there are no black out zones on the north and south wings of the building. All desktops, laptops, and servers will require physical locks in addition to virtual lock screens in place. All desktops and laptops will also require a notification upon being powered on to inform the user that they are subject to persecution under law should illegal or otherwise banned activities occur during use of the device. Prior to employment at the new location employees must sign a contract that informs them of what acceptable behavior is when using the devices on site as well as any other technical restrictions they must follow.

Change Request Form effective 12/20/2018:

The first level will include a path from the north and south wings to allow for continuous network connectivity. This will allow users to connect to the network and walk from one end of the building to the other without entering a black out zone.

VI. Exclusions from Scope	*List all deliverables or requirements that are not part of this project.*

Biometric measures may be implemented at a later date to improve security; however, at this time this will not be part of this particular network project.

VII. Time and Cost Estimates	*Include initial estimates of time and resources. These are estimates only and will be updated after additional project planning activities are completed.*

This project budget will include computer costs for roughly 500 employees who will not be sharing devices for security reasons. Assuming bulk discounts are applied, and a mixture of laptops and desktops will be purchased, the estimated cost for computers alone will be $250,000 (Thompson, 2017). Installing these devices along with the appropriate security measures will take roughly two weeks. Network security software will need to be installed on each of the company owned devices. As an estimate, Avast offers businesses a one-year contract for 200 devices at just over $5,100 a year which would be roughly $8,200 for all 500 devices (Avast Software, Inc., 2018). Three servers will also need to be installed and will take roughly one week to setup with a cost estimate of $1,800 (Gildred, 2018). Cabling will need to be installed throughout the building to allow the computers and servers to connect to the network. Installing the cabling for this network will take roughly three weeks and cost roughly $10,500 if Cat7 cabling is used (Fixr, 2018). Outside of the network cabling all other network hardware will take roughly one week to install. Additional costs will include the 15 access points for users to connect to the network. These access points will cost a little over $2,500 and possibly more after taxes and after the network speeds are tested (Linksys, 2018). This may also be reduced once routers are in place. An estimate of two routers will be needed for ensuring the network has a failover for the primary ISP going down which will cost roughly $700 (Hyde, 2018). Assuming that each user needs 2 ports to connect a computer and monitor a total of 1,000 ports will be needed for users to connect to the network. Taking this into account the price for the switches needed will cost a minimum of $52,000 (ALLHDD, 2018).

Change Request Form effective 12/20/2018:

Adjusting the first floors network configuration will add roughly two days onto the schedule. Taking this into consideration it will take approximately four and a half weeks to install and configure the network.

VIII. Roles and Responsibilities *Include a roles-and-responsibilities chart, detailing project responsibilities.*

Roles	Responsibilities
Project Manager	• Manage project resources • Manage project team members • Monitor & report project progress • Manage relationship with vendors & stakeholders • Document team meetings • Document lessons learned • Attend all stakeholder and team meetings. • Develop plans of action for team members or vendors not meeting the set expectations.
Agenda Director	• Assist PM with developing the project's schedule. • Communicate project development with the PM. • Monitor team member progress and report to PM. • Document changes to schedule. • Assist PM with developing action plans in the event that there are scheduling issues. • Coordinate stakeholder meetings. • Coordinate weekly team progress meetings.
Systems Analyst	• Analyze current network trends • Evaluate vendor options • Develop network design • Evaluate physical security needs
Network Engineer	• Install hardware & cabling • Complete all hardware configuration • Report completions or complications
Software Engineer	• Install necessary software onto all devices • Implement software related security features
Testing Engineer	• Develop testing plan • Implement unit testing for network • Implement unit testing for all devices • Analyze testing results • Report testing results • Develop plan of action for any issues discovered

(TARGET postgrad, 2018)

IX. Assumptions *List all project assumptions.*

- Installing computers, software, and security measures will take two weeks.
- Installing the servers will take only one week.
- Installing the cabling will take three weeks.
- Only 15 access points and 2 routers will be needed to give the employees the desired network speeds.
- All devices will be compatible with one another and the software installed.
- All employees will be available during their scheduled work hours.
- All vendors will fulfill their contractual obligations.
- The necessary resources to complete this project will be available when needed.
- Communication throughout the project will occur daily between team members.
- All stakeholders will attend the required meetings.
- Penetration has been completed to ensure that the appropriate security measures are in place.

Change Request Form effective 12/20/2018:

Adjusting the first floors network configuration will not require additional equipment but rather equipment to be rearranged.

X. Product Acceptance *List all project acceptance criteria.*
Criteria

- The top two floors provide 100% network coverage.
- The first floor provides 100% network coverage to the north and south wings.
- The network speeds provide each user 30 Mbps upload and 10 Mbps download.
- There are separate servers dedicated to critical employee data and for customer data.
- Each computer is equipped with a warning message regarding device use when powered on.
- Each computer is equipped with an antivirus software.
- Each computer has the appropriate firewall rules and ports available.
- Users are able to begin testing their devices functionality by December 1st.
- Full network testing has been documented to ensure functionality to employees.

Change Request Form effective 12/20/2018:
The first floor will provide 100% network coverage to the north and south wings as well as a path of full connectivity to and from either wing.

XI. Constraints *List all project constraints.*

- The project must stay under $600,000.
- The project must be completed by December 30th.
- The project will not be worked on during Christmas Eve or Christmas Day.
- There will only be three networking engineers available.
- There will only be two software engineers available.
- There will only be one testing engineer, systems analyst, and agenda director available.
- Computers and software must be installed no later than November 30th.
- Network cabling & hardware must be installed no later than December 20th.

XII. Signatures *Include signature lines for the project sponsor, project manager, key stakeholders, customers, and vendors.*

X _____	X _____	X _____
Project Manager	Project Sponsor	ISP
X _____	X _____	X _____
Stakeholder	Stakeholder	Stakeholder
X _____	X _____	X _____
Cabling Vendor	Hardware Vendor	Software Vendor

References

ALLHDD. (2018). WS-C3850-48P-S Cisco Catalyst 3850 48 Port PoE IP Base. New Bulk Pack. Retrieved from https://www.allhdd.com/networking/switch/48-port/ws-c3850-48p-s-cisco-catalyst-3850-48-port-poe-ip-base.-new-bulk-pack./?src=ggl&gclid=EAIaIQobChMI3cmHkZP23gIVqh6tBh2wxgXuEAQYAiABEgJnz_D_BwE

Avast Software Inc.. (2018). Avast Business Antivirus Pro Plus. Retrieved from https://www.avast.com/en-us/business/products/business-antivirus-pro-plus

Fixr. (2018). Hardwired Computer Network Cost. Retrieved from https://www.fixr.com/costs/hardwired-computer-network

Gildred, J. (2018, May 14). 5 Best Affordable Servers for Small Businesses. Retrieved from https://www.cloudwards.net/best-small-business-server/

Heldman, K. (2011, May 5). Project Management JumpStart, 3rd Edition. [Purdue University Global Bookshelf]. Retrieved from https://purdueuniversityglobal.vitalsource.com/#/books/9781118094471/

Hyde, P. (2018, November 23). The 7 Best Small Business Routers to Buy in 2018. Retrieved from https://www.thebalancesmb.com/best-small-business-routers-4171956

Kaleem, Z. (2017, May 18). How to Estimate Number of Access Points Needed for WiFi Projects. Retrieved from https://www.accessagility.com/blog/how-to-estimate-number-of-access-points-needed

Linksys. (2018). Linksys LAPN600 Business Access Point Wireless Wi-Fi Dual Band 2.4 + 5GHz N600 with PoE. Retrieved from https://www.linksys.com/us/p/P-LAPN600/

TARGET postgrad. (2018). IT Job Roles and Responsibilities Explained. Retrieved from https://targetpostgrad.com/subjects/computer-science-and-it/it-job-roles-and-responsibilities-explained

Thompson, E. (2017, June 18). How Much Should a Business Computer Cost? Retrieved from https://www.business.org/finance/cost-management/much-computer-cost/